



Advanced Utilities Limited

Project Profile

Rampton Hospital

Client:
NHS
Carillion
Crown House

Location:
Rampton,
Nottinghamshire

Project Details:
New Secure Women's
Unit

Value:
£350,000.00

Duration:
9 Months

We competitively tendered the project to both Carillion and Crown House Technologies.

The Carillion package involved excavations, break-ins, and reinstatement on both the live secure hospital site and the construction site. Security clearances were required for our staff and operatives and extensive site restrictions were applied whilst working on the live side.

The Crown House Technologies package involved the installation of 315mm Gas Main, 180mm Fire Main plus ancillary mains Cold Water, Electrical and Communications ducting. The connections onto the existing services were critical to both the new Women's Unit and the existing Secure Hospital. Close liaison was required with the existing works department and the site team. Contingencies were put in place to ensure that should the break-ins not go to plan then the existing supplies could be maintained.

The construction site works were successfully undertaken with a multi service approach to minimise disruption on a very challenging site, as the available space was very limited and the programme very tight.